

MAR 12 1999

LIBER 2085 PAGE 1404

SECTION

APPROVED BY PEER GROUP 1998 REMONUMENTATION PROGRAM
P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE
SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

John H. Rauser
9-30-98
For corners in

Saginaw Located In: Chapin Twp. Corner Code # G-13
(County)

- 1. Public Land Survey T 9N R 1E G-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on July, August & September 19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5					4	3		2			1
3													
4	7	8					9	10		11			12
5													
6	18	17					16	15		14			13
7													
8	19	20					21	22		23			24
9													
10	30	29					28	27		26			25
11													
12	31	32					33	34		35			36
13													

File 7 Page 263

1998 OCT 13 P 2:10
MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.
RECORDED/FILED
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:
G-13 Standard 1/4 Corner, Section 34, T9N-R1E, Chapin Township

- 1831 GLO wood post placed by Robinson Thomas, D.S.
Lynnwood 12" N18°E 33 links
Beech 8" N33°W 45 links
- 1850 Shiawassee County Survey Book A P.17 listed GLO witnesses.
- 1878 County Survey by Lyman Mason, county record 1874-1883 P.158. Calls for jog G13 to G1, T8N-R1E, 102 links (67.32').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-13 Standard 1/4 Corner, Section 34, T9N-R1E, Chapin Township

Found no evidence of the original government corner or county surveyor evidence. Found 1/2" re-rod at the position of G-1, T8N-R1E, Shiawassee County, this position was not established during the original government, due to impassable land, therefore no GLO closing was noted. In 1878 Shiawassee County Surveyor Lyman Mason who noted the closing distance of 102 links. Found no evidence of the corner. The closing distance from the found rod at G-1 measured East falls in the approximate centerline of Fenner Road. Measured G-13 to F-13, 2640.63' (GLO = 2640, C.S. 2645.94'); H-13 to G-13, 2646.37 feet. 1878 Shiawassee County Survey by Lyman Mason C.S. measured G-13 to H-13 and H-13 to I-13, 2639.51. Found no conflicting evidence in the vicinity of this position. Accepted this position as the best available evidence of the position of the original government corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-13 Standard 1/4 Corner, Section 34, T9N-R1E, Chapin Township

Placed 5/8" re-rod with standard Saginaw County brass cap stamped "G-13 1998 39096", and monument box.

- West 37.32' Found 1/2" re-rod at position G-1, T8N-R1E
- West 13.10' North edge of Gas Marker
- N45°W 33.40' South face of 6" Pine
- N85°E 30.80' Found nail w/tag #22445 in N. face of P/P
- S88°E 37.26' Set spike w/tag #39096 in S face P/P

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

