

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8 10

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

2-21 BOA  
For corners in

<u>Saginaw</u> (County)	Located In: Chapin Twp.	Corner Code #		
1. Public Land Survey	T <u>9N</u>	R <u>1E</u>	<u>H-11</u>	
2. Property Controlling in Section	S <u>    </u> T <u>    </u>	R <u>    </u> R <u>    </u>	<u>    </u> <u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u>	R <u>    </u> R <u>    </u>	<u>    </u> <u>    </u>	
4. Lot No. <u>    </u> , Recorded Plat <u>    </u>				
5. Private Claims <u>    </u>	SECTION <u>    </u>			

LIBER 2144 PAGE 1449

*Lib 8 Page 71*  
Register of Deeds Stamp & File Number

SEP 29 2000

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on September 28 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11 1/4 Corner, Sections 27, & 34, Chapin Township

1831 GLO wood post placed by Robinson Thomas, D.S. at a split distance of 39.92 chains (2634.72')  
N46W 29lks (19.14') 10" Beech  
S66E 13lks (8.58') 16" Beech

No subsequent record of restoration or perpetuation

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 1/4 Corner, Sections 27, & 34, Chapin Township

Found no evidence of the original government accessories. Found 3" round steel pipe in concrete base leaning North in fence N-E-W, 10'+ North of the centerline of a drain. Also found wood post West, 1.0' of steel pipe and 2" angle iron 4' tall in concrete base with old wood post on North side and fence running south, South, 34.8' of the 3" pipe. Measured East to I-11, 2641.38' and measured West to G-11, 2641.51' both from the 3" iron pipe. The 3" pipe falls 2.2' South of a line between J-11 and I-11 extended West and 24.1' North of a line between G-11 and I-11. We recommend that found 3" steel pipe in concrete be accepted as the best available evidence of the position of the original government corner and reference irons be set on the section line East and West of this accepted position. During removal of a tree which had fallen over the found 3" steel fence post, the fence post broke off 2" above concrete base. Set the standard Saginaw County 5/8" re-rod (3' long) with brass cap in the inside the base of the post. Set one reference rod with brass cap stamped "REF PT 10 FT".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 1/4 Corner, Sections 27, & 34, Chapin Township

Set 5/8" X 3' re-rod with standard Saginaw County brass cap stamped "H-11 39096" inside the base of a 3" steel fence post.  
S88W 10.00' 5/8" X 3' re-rod with Saginaw County brass cap stamped "REF PT 10 FT" with arrow "—>" to H-11  
South 34.75' Found 2" angle iron fence post  
N09E 23.14' 1/2" re-rod with ROWE traverse cap  
N69E 12.62' Set spike with ROWE witness tag in N face of 18" Hickory

Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

