

MAR 12 1999

SECTION

LIBER 2085 PAGE 1401

APPROVED BY PEER GROUP 1998 REMONUMENTATION PROGRAM
P.A. 345 OF 1990
SAGINAW COUNTY
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

BOA 9-30-98

For corners in

Saginaw Located in: Chapin Twp. Corner Code # H-13
(County)

RECORDED/FILED
1998 OCT 13 P 2:10
MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.
Lib 7 Page 260
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 9N R 1E H-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. Recorded Plat
- 5. Private Claims

I, John H. Rauser, P.S., in a field survey on July & August 19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
H-13 Standard 1/4 Corner, Section 34, T9N-R1E, Chapin Township

- 1831 GLO wood post placed by Robinson Thomas, D.S.
Lynnwood 12" N18°E 33 links
Beech 8" N33°W 45 links
- 1850 Shiawassee County Survey Book A P.17 listed GLO witnesses.
- 1878 County Survey by Lyman Mason, county record 1874-1883 P.158. Calls for jog H-13 to H-1, T8N-R1E, 114 1/4 links (75.405').
- 1926 Shiawassee County Road Book 15, P.176 by E.F. Joslin, C.S. Calls for 1 1/4" wellpoint at H-1, T8N-R1E, & notes 1.14 ch West of Saginaw County Corner.
- 1971 Act 132 by J.F. Quine, L. 1, P. 40, Section 3, T8N-R1E, calls for 24" Bitternut Hickory at corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-13 Standard 1/4 Corner, Section 34, T9N-R1E, Chapin Township

Found no evidence of the original government corner or county surveyor evidence. Found 30" Bitternut Hickory with fence N-S & W in line with monumentation as recorded in L.1, P.40 Shiawassee County Records 4.13' South of a line between I-13 & G-13, T9N-R2E. Measured H-13 to I-13, 2648.32 (1971 Quine = 2648.02); H-13 to G-13, 2646.37 feet. 1878 Shiawassee County Survey by Lyman Mason C.S. measured G-13 to H-13 and H-13 to I-13, 2639.51. Found no conflicting evidence in the vicinity of this position. Accepted this position as the best available evidence of the position of the original government corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13 Standard 1/4 Corner, Section 34, T9N-R1E, Chapin Township

Placed 5/8" re-rod with standard Saginaw County brass cap stamped "1998 h-13 39096" inside 1" pipe 2' long, in the center of the stump of the Bitternut Hickory which has blown over
N5°E 17.80' Set spike w/tag 39096 in the E. face of 10" twin Ash
S5°W 24.77' Set spike w/tag 39096 in the W. face of P/P
S40°E 94.10' Set spike w/tag 39096 in the SW. face of Poplar
West 0.40' Set carsonite survey marker post
South 110' Centerline of Ridge Road

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

