

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8:09

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

For corners in

<u>Saginaw</u> (County)	Located In: Chapin Twp.	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>1E</u> I- <u>11</u>
2. Property Controlling in Section	S _____ S _____	T _____ T _____ R _____ R _____
3. Miscellaneous Property in Sec.	S _____ S _____	T _____ T _____ R _____ R _____

LIBER 2144 PAGE 1440

Liber 8 Page 62
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on September 20 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-11 Section Corner, Sections 26, 27, 34, & 35, Chapin Township

1831 GLO wood post placed by Robinson Thomas, D.S.
S72E 10lks (6.6') 14" Lynn
N14W 13lks (8.58') 10" Elm

GLO distances 2640 North & South, 2646.60 East and 2634.72 West.

1991 Field notes from Spicer Group, found large nail w/ribbon at bit. surface, set 3/4" solid iron bar over same. Measured East to J-11 = 2643.31 feet and South to I-12 2691.34'.

N45E 30.75' NE cor conc. headwall
N45W 43.30' Face of T/P
S45E 31.38' SE cor E end curved headwall

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Section Corner, Sections 26, 27, 34, & 35, Chapin Township

Found no evidence of the original government accessories. Found 1" iron bar with out monument box at the intersection of centerlines of Kramer Road to the East and Merrill Road to the North and South. Found no existing witness tags or conflicting evidence in the vicinity of this position. Measured South to I-12, 2691.20', North to I-10, 2629.10', West to H-11, 2641.38' and East to J-11, 2643.07'. We recommend that the found 1" iron bar be accepted as the best available evidence of the position of the original government corner and be replaced with a standard Saginaw County 5/8" re-rod with brass cap in a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Section Corner, Sections 26, 27, 34, & 35, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "I-11 39096" and monument box

N76E 148.46' Set PK nail/tag #39096 in S fc PP
N54W 43.50' Set PK nail/tag #39096 in S fc PP
S78W 18.70' S edge of S'ly leg of dbl arrow sign
S49E 44.98' W edge of street sign post

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date _____

