

RECORDED/FILED

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8:09

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

For corners in

<u>Saginaw</u> (County)	Located In: Chapin Twp.	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>1E</u> <u>K-11</u>
	T _____	R _____
2. Property Controlling	S _____	R _____
in Section	S _____	R _____
3. Miscellaneous	S _____	R _____
Property in Sec.	S _____	R _____

LIBER 2144 PAGE 1437

*Liber 8 Page 59*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on September 20 19 99.

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-11 Section Corner, Sections 25, 26, 35, & 36, Chapin Township

- 1831 GLO wood post placed by Robinson Thomas, D.S.
- 1972 Act 132 Certified Survey by Oliver M. Elliot, RLS #2097 as recorded on L.1369, P.470
- 1977 Road Commission Witness Cards
- 1991 Field notes from Spicer Group, found large boat spike 1" below bit. surface. Measured West to J-11 = 2710.82 and South to K-12 = 2648.68'.

- N45E 50.84' Face of P&T pole
- N65W 98.0' Face of P&T pole
- S50W 119.80' Face of power pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 Section Corner, Sections 25, 26, 35, & 36, Chapin Township

Found no evidence of the original government accessories. Found boat spike without monument box at the centerlines of Chapin Road and Kramer Road. Found and checked one witnesses from the 1977 Road Commission witnesses. Measured South to K-12, 2648.49', measured East to L-11, 2614.13 and measured West to J-11, 2710.73. Found no conflicting evidence in the vicinity of this corner. We recommend that the found boat spike be accepted as the best available evidence of the position of the original government corner and be replace with a standard Saginaw County 5/8" re-rod with brass cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 Section Corner, Sections 25, 26, 35, & 36, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "K-11 39096" and monument box

- S64E 37.11' N edge of street sign post
- N42E 51.21' Set PK/tag #39096 SE fc PP ( R = 51.24' and 50.84' to face)
- N74W 98.37' Set PK/tag #39096 S fc PP ( R = 98' to face)
- S62W 32.76' N side stop sign post

Signed by John H. Rauser  
Surveyor's Michigan License No. 39096

Date \_\_\_\_\_

