

RECORDED/FILED

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 SEP 30 A 8:09
MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

LIBER 2144 PAGE 1434

Lib 8 Page 56
Register of Deeds Stamp & File Number

For corners in

<u>Saginaw</u> (County)	Located in: Chapin Twp.	Corner Code #
1. Public Land Survey	T <u>9N</u>	R <u>1E</u> <u>M-11</u>
	T _____	R _____
2. Property Controlling in Section	S _____	T _____
	S _____	T _____
3. Miscellaneous Property in Sec.	S _____	T _____
	S _____	T _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John H. Rauser, P.S., in a field survey on September 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Standard Corner, Sections 25 & 36, Chapin Township

1831 GLO wood post placed by Robinson Thomas, D.S.
S52W 5lks (3.30') 6" W. Oak
N60E 21lks (13.86') 6" Ash

No subsequent record of restoration or perpetuation.

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Standard Corner, Sections 25 & 36, Chapin Township

Found no evidence of the original government accessories. Found no object at the position of the corner. Found the closing corner at A-10, T9N-R2E and the standard 1/4 corner at M-12, T9N-R1E. Using collateral evidence of the occupation line between M-11 and M-12, T9N-R1E, which measured 1311.62 feet North of the found M-12, this distance was doubled over for a measurement of 2623.24' from M-12 to M-11 and placed on line between M-12 and A-10. This measurement is in agreement with the measurement M-12 to M-13 of 2622.40'. Measurement to A-10 = 2652.14', applying a mean GLO closing jog (64lks at A-9 and 24lks at A-11) at A-10 to M-10 of 44lks (29.04') the measurement to M-10 = 2623.10'. The calculated position of M-11 measures West to L-11 = 2615.86 feet. This measurement is in comparison with K-11 to L-11 = 2614.13'. L-11 falls 1.92' south of a line between found K-11 and calculated M-11. Found no conflicting evidence in the vicinity of this corner. Calculated position falls 7'+ West of center line of Steel Road and 12'+ South of Kramer Road. Measured North 16'+ to an occupied field line to the East. We recommend that the position established with the use of existing collateral evidence be accepted as the best available evidence of the position of the original government corner and a standard Saginaw County 5/8" re-rod with brass cap be placed in a monument box at this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Standard Corner, Sections 25 & 36, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "M-11 39096" and monument box
N65E 19.37' 1/2" re-rod with ROWE traverse cap, East of East edge of asphalt
N30E 49.80' T/C of East end 36" cmp
N20W 47.72' T/C of West end 36" cmp
West 26.46' N. edge of stop sign post
N80E 21.42' S. edge of S. lag <-> sign post

Signed by John H. Rauser
Surveyor's Michigan License No. 39096

Date _____

