

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

1999 SEP 30 A 8:08

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

For corners in

Saginaw (County) Located In: Chapin Twp. Corner Code #

LIBER 2144 PAGE 1433

*Liber 8 Page 55*  
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 9N R 1E M-12  
T \_\_\_\_\_ R \_\_\_\_\_ M- \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John H. Rauser, P.S., in a field survey on September 17 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 Standard 1/4 Corner, Section 36, Chapin Township

- 1831 GLO wood post placed by Robinson Thomas, D.S.
- 1973 Act 74 by Robert L. Mitchell, LS #6936 as recorded on L.2, P.222
- 1973 Act 132 Certified Survey by Robert L. Mitchell, LS#6936

RAUSER &  
REGISTERED PROFESSIONAL SURVEYOR

MAR 09 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Standard 1/4 Corner, Section 36, Chapin Township

Found 3/4" pipe in centerline of Steel Road and in center line of ditch to West. Measured South to M-13 = 2622.40 ( R = 2625.20'); measured North to an occupied fence line to the West 1311.62' and 2623.24' to re-established M-11. Found reference iron from record 1973 survey at the Southwest corner of Ridge and Steel Roads which is 33.1' West of a line from M-12 to M-13 ( R = 33'). Found no conflicting evidence in the vicinity of this position. We recommend that the found 3/4" pipe be accepted as the best available evidence of the original government corner and be replaced with a standard Saginaw County 5/8" re-rod with brass cap in a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Standard 1/4 Corner, Section 36, Chapin Township

Set 5/8" re-rod with standard Saginaw County brass cap stamped "M-12 39096" and monument box.

- S89W 20.85' Top center W end 15" CMP
- S89E 18.82' Top center E end 15" CMP
- N17E 84.46' Set PK/tag #39096 in W fc PP
- S13E 146.32' Set PK/tag #39096 in W fc PP

Signed by John H. Rauser Date \_\_\_\_\_  
Surveyor's Michigan License No. 39096

