

MAR 12 1999

SECTION

LIBER 2085 PAGE 1397

APPROVED BY PEER GROUP 1998 REMONUMENTATION PROGRAM
P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE
SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

Like 7 Page 254

B.W. 8-19-98

1998 OCT 13 P 2:09
MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

RECORDED/FILED

Register of Deeds Stamp & File Number

Saginaw Located In: Brady Twp. Corner Code # D-13
(County)

- 1. Public Land Survey T 9N R 2E D-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. Recorded Plat
- 5. Private Claims

John H. Rauser, P.S. in a field survey on July & August 19 98
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-13 South 1/4 Corner, Section 32, T9N-R2E, Brady Township

- 1824 GLO wood post placed by William Brookfield, D.S.
Beech 12" N78°E 10 links
Sugar 18" S76°W 14 links
- 1887 County Survey by H.C. Main, C.S. P.176, Book 1879-1900. Found & witnessed 1/4 post to Saginaw County during survey of Sec. 5, T8N-R2E.
W. Oak 6" S30°W 49 1/2 links
120 1/2 links N89°W of D-1, T8N-R2E
- 1972 Act 74 by John W. Martin, L.1, P.217, set nail. Listed 2 witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-13 South 1/4 Corner, Section 32, T9N-R2E, Brady Township

Found 3/4" pipe 2± N of E-W centerline gravel to North. One 1972 witness remains R=NE 64.80' to Fc of 6" Cedar (M=64.5' Fc of 15" Cedar), road sign post has been replaced. Measured East 81.8± to occupied field line to South, (C.S. R=120 1/2 links (79.53')) found old nail & small stone in road at position approximately 80' East. Fence tree line approximately 1000' South of closing corner fits good. White Oak witness to closing corner is gone. Found no evidence of GLO Accessories or other conflicting evidence at the standard position of D-13. We accept the position of the 3/4" pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-13 South 1/4 Corner, Section 32, T9N-R2E, Brady Township

- Replaced 3/4" pipe with 5/8" re-rod and standard Saginaw County brass cap stamped "1998 D-13 39096"
- N30W 34.62 Easterly edge of stop sign post
- N20E 64.35 Southerly face of 15" cedar
- N50E 96.05 SW corner of block porch @ house #17949
- N45E 53.75 Set PK w/tag #39096 in w'ly root of 24" poplar

Signed by *John H. Rauser*
Surveyor's Michigan License No. 39096

