

SECTION

LIBER 2085 PAGE 1396

APPROVED BY PEER GROUP 1998 REMONUMENTATION PROGRAM  
P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE  
SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

*Lib 7 Page 255*

*BDP 8-19-98*  
of corners in

1998 OCT 13 P 2:09  
MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.  
RECORDED/FILED

Saginaw Located In: Brady Twp. Corner Code # E-13  
(County)

Public Land Survey T 9N R 2E E-13  
T R  
T R  
T R  
Property Controlling S T R  
in Section S T R  
Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

Lot No. Recorded Plat  
Private Claims

John H. Rauser, P.S., in a field survey on July & August 19 98  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
court of Law, established, re-established, monumented, re-monumented, recovered, found as  
expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**Description of original monument and accessories and/or subsequent restoration:**  
E-13 Common Corner, Section 32 & 33, T9N-R2E, Brady Township

- 1824 GLO wood post placed by William Brookfield, D.S.  
Sugar 9" N68°E 20 links  
Beech 9" S47°W 4 1/2 links
- 1850± Shiawassee County book A and other un-recorded survey, SE corner Section 32, T9N-R2E, listed GLO witnesses.
- 1996 Field notes from Spicer Engineering Job #S-96-091. Found pipe.

**Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
E-13 Common Corner, Section 32 & 33, T9N-R2E, Brady Township

Found no evidence of original Government corner. Found 3/4" pipe with mushroom head in centerline of Brennan Road to north and in centerline of Johnstone Road E-W. Found E-1, T8N-R2E, Shiawassee County East 153.71' (GLO=231 lks 152.46) 1/2" rod in centerline of Ruess Road to south. Found no conflicting evidence near this position. Measured West to D-13, 2620.60' (2627.96' = Spicer) and East to F-13, 2603.88' (2608.84' = Spicer) Accepted the position of found 3/4" pipe as the best available evidence of the original government corner.

**Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
E-13 Common Corner, Section 32 & 33, T9N-R2E, Brady Township

- Replaced 3/4" pipe with 5/8" re-rod and standard Saginaw County brass cap stamped "1998 E -13 39096".
- N45°W 42.36' Set PK w/tag #39096 S. face P/P
- N50°E 43.81' Set PK w/tag #39096 W. face P/P
- East 153.70' 1/2" Rod E-1, T8N-R2E
- South 16.13' East edge east leg of ↔ sign

Signed by *John H. Rauser*  
Surveyor's Michigan license No. 39096



*10/07/98*