

MAR 12 1999

LIBER 2085 PAGE 1395

SECTION

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 7 Page 254

BOF 8-19-98
For corners in

Saginaw Located in: Brady Twp. Corner Code # G-13
(County)

- 1. Public Land Survey T 9N R 2E G-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

1998 OCT 13 P 2:09
MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI
RECORDED/FILED
Register of Deeds Stamp & File Number

I, John H. Rauser, P.S., in a field survey on July & August 19 98
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				4		3		2			1
3													
4	7	8				9		10		11			12
5													
6	18	17				16		15		14			13
7													
8	19	20				21		22		23			24
9													
10	30	29				28		27		26			25
11													
12	31	32				33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:
G-13 Standard 1/4 Corner, Sections 33 & 34, T9N-R2E, Brady Township

- 1824 GLO wood post placed by William Brookfield, D.S.
Ironwood 5" S82°E 5 links
Sugar 8" N27°W 12 links
- 1850 County survey Book "A" listed GLO witnesses.
- 1974 CP Co. Survey by Glen A. Fauser L.1421, P.857, found 5/8" iron bar in intersection of centerlines of roads E-W-N. Listed 4 witnesses.
- 1996 Field notes from Spicer Engineering Job #S-98-091.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-13 Standard 1/4 Corner, Sections 33 & 34, T9N-R2E, Brady Township

Found 5/8" bar in gravel road, on E-W-N centerline. Found G-1, T8N-R2E, East 112.75' (GLO=170 lks = 112.2'). Found and checked 3 witnesses from Cp Co. record; P/P, N19°W, 76.30' (M=76.28'); SW corner garage, N48°E, 126.00' (M=126.00'); Street sign E leg, S01°W, 12.67' (M=12.63'). Measured West to F-13, 2603.00' (2602.96' = Spicer). Found no GLO accessories or other corners conflicting with this position. We accept the position of the 5/8" bar as the best available evidence of the position of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-13 Standard 1/4 Corner, Sections 33 & 34, T9N-R2E, Brady Township

Left 5/8" iron bar in place with standard Saginaw County brass cap stamped "1998 G-13 39096".

- N19°W 76.30' Found PK with tag in S Fc P/P
- N48°E 126.00' SW Corner garage (brick)
- S01°W 12.67' E'ly leg Street sign
- East 112.75' G-1, T8N-R2E, 1/2" rod

Signed by John H. Rauser
Surveyor's Michigan License No. 39096



10/07/98