

MAY 18 1999

LIBER 2085 PAGE 1393

SECTION

1998 REMONUMENTATION PROGRAM

APPROVED BY PEER GROUP

LAND CORNER RECORDATION CERTIFICATE

*Lib 2085 Page 252*

P.A. 345 OF 1990

Filing Requirement of Act 74, Mich. P.A. 1970

SAGINAW COUNTY

*BA 8-19-98*

1998 OCT 13 P 2:09  
MILDRED H. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI

RECORDED/FILED

Register of Deeds Stamp & File Number

of corners in

Saginaw Located In: Brady Twp. Corner Code # H-13

(County)

Public Land Survey T9N R2E H-13

T R

T R

T R

Property Controlling in Section S T R

Miscellaneous S T R

Property in Sec. S T R

Lot No. Recorded Plat

Private Claims

John H. Rauser, P.S. in a field survey on July & August 19 98

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13 South 1/4 Corner, Section 34, T9N-R2E, Brady Township

- 1824 GLO wood post placed by William Brookfield, D.S.  
W. Oak 30" N35°E 12 links  
W. Oak 30" S73°W 9 links
- 1850 Witnesses from Shiawassee County Book "A" used recorded GLO witnesses.
- 1878 Shiawassee County Survey Book "D" P.174-175. Shows 200 links jog at 1/4 corner to H-1, T8N-R2E. No witnesses to standard corner H-13.
- 1974 CP Co. Survey by Glen A. Fauser L.1421, P.657. Set 1/2" re-bar listed 3 witnesses & centerline road ties.
- 1983 Act 132 by J.S. Fokens L.1627, P.853. Found 1/2" rered with unreadable cap, listed 4 witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 South 1/4 Corner, Section 34, T9N-R2E, Brady Township

Found no evidence of original government accessories or county survey. Found 1/2" rered bent over, 0.9'± South of centerline 131.98' (C.S.=200 lks = 132') West of H-1, T8N-R2E, & 9'± East of end of pavement. Two witnesses from 1983 were gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 South 1/4 Corner, Section 34, T9N-R2E, Brady Township

Replace 1/2" rod with 5/8" re-rod and standard Saginaw County brass cap stamped "1998 H-13 39096"

- North 0.9' Centerline of Johnstone Road
- East 131.98' H-1, Section 3, T8N-R2E
- West 9' End of asphalt pavement
- S40W 65.30' Set spike/tag #39096 in NW. face 8" Oak
- S45E 51.72' Set spike/tag #39096 in W. face 6" Hickory

Signed by Surveyor's Michigan License No. 39096

*John H. Rauser*



*10/07/98*