

MAR 2 1999

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LIBER 2084 PAGE 239

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MILDRED M. DODD  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

1998 OCT -5 A 9:53

RECORDED/FILED

For corners in

<u>SAGINAW</u> (County)	Located in: BRADY TWP	Corner Code #
1. Public Land Survey	T <u>9N</u> R <u>2E</u>	<u>L-13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Liber 7 Page 217*  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Brian D Ferguson, in a field survey on SEPTEMBER 25, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		5		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-13 WOOD POST SET BY WILLIAM BROOKFIELD, DEPUTY SURVEYOR, IN 1823  
20" ELM N48°E 34 LINKS  
11" WHITE OAK N82W 14 LINKS  
NO EVIDENCE OF ORIGINAL CORNER REMAINS  
NO LCRC'S OR SURVEYS RECORDED FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 FOUND 3/4" PIPE AT LOCATION REFERRED TO BY NOTES OF MDOT SURVEYOR C.E. SMITH IN 1962 WHILE SETTING CORNER FOR L-1, T8N-R2E. CALL WAS FOR 104.28 FEET BETWEEN CORNERS, MEASURED 104.32 FEET DISTANCE TO K-13 MEASURED AT 2620.30 FEET, TO M-13 AT 2623.86 FEET  
NO PHYSICAL OCCUPATION TO NORTH

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX  
S06°E 40.54' SET NAIL & SHINNER E FACE 10" ASPEN  
S48°W 40.37' SET NAIL & SHINNER E FACE 6" ASPEN  
N48°W 54.23' SET NAIL & SHINNER E FACE 4"X4" POST  
S62°E 60.98' FACE STEEL R.R. SIGN POST  
WEST 104.32' 3/4" PIPE, L-1, T8N-R2E

Signed by Brian D Ferguson  
Surveyor's Michigan License No. 26454

Date SEPTEMBER 28, 1998

