

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

BDJ 9-16-98

For corners in

SAGINAW (County) Located in: CHESANING TWP Corner Code #

1. Public Land Survey	T <u>9N</u> R <u>3E</u>	<u>C-13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D Ferguson, in a field survey on AUGUST 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13 WOOD POST SET BY JOHN MULLETT, DEPUTY SURVEYOR, IN 1840
9" SUGAR S60°E 11 LINKS
30" SUGAR N02°W 9 1/2 LINKS
NO EVIDENCE OF ORIGINAL POST REMAINS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 FOUND 3/4" PIPE IN INTERSECTION OF JOHNSTONE RD AT FRANDSCHE RD
NO LCRC'S RECORDED FOR THIS CORNER
LOCATION AGREES WITH NOTES FROM SPICER GIVING DISTANCE TO C-12 AND B-13 AND ANGLE B-13, C-13, C-12
LOCATION AGREES WITH SURVEY BY LANTZ-GRIGGS USING CORNER AS WITNESS TO C-1, T8N-R3E
SCRC WITNESSES FROM 1983 HAVE TIE OF N40°E 41.52' TO FACE OF ST SIGN POST. MEASURED 41.98'

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX
N38°W 42.96' NEAREST PART OF STOP SIGN POST
S33°W 50.05' NEAREST PART OF STOP SIGN POST
N42°E 41.98' NEAREST PART OF ROAD SIGN POST
S53°E 25.20' SET 1/2" ROD W/CAP 26454

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date SEPTEMBER 24, 1998

RECORDED/FILED
1998 OCT -5 A 9:53
FILED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

Liber 7 Page 220
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

