

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT
 SAGINAW COUNTY LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 7 Page 101

For corners in
Saginaw Located In: _____ Corner Code # _____
 (County)
 Chesaning Township

1. Public Land Survey	T	9N	R	3E	E-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

REGISTERED & FILED
 SEP 27 3 16 PM '96
 HILDRED M. GUDAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.
 Register of Deeds Stamp File Number

I, John H. Rauser, in a field survey on February 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-3 Sec. Cor., Sec. 4, 5, 8 & 9, T9N-R3E
 1822 wood post placed by J. Wample
 Ash 9" S45 1/2°E, 6 lks (3.96')
 Elm 14" S63°W, 8 lks (5.28')
 1878 County survey by H.G. Ives, Deputy County Surveyor
 B. Ash 12" S10 1/2°W 43 1/2 lks (28.71')
 W. Oak 24" S9 1/2°E 92 lks (60.72')
 1956 Spicer Engineering Field Note Witnesses
 1968 Edmond's Engineering C.P.C.O. Survey
 1973 Saginaw County Road Commission Records, found 3/4" pipe; later placed a monument box
 1975 L.C.R.C. by R.L. Mitchell, P.S. #6936, Rec. L. 3, P. 103, Saginaw County Records
 1977 L.C.R.C. by M.L. Vanraemdonck, P.S.#24622 Rec. L.4,P.108, Saginaw County Records
 1982 Act 132 survey by M.L. Vanraemdonck, P.S. #24622, Rec. L. 1622, P. 1160, Saginaw County Records
 1992 Spicer Engineering Field Note Witnesses
 1994 Act 132 survey by J.S. Fokens, P.S. #21567, Rec. L. 1956, P. 1282, Saginaw County Records
 1995 Act 132 survey by M.L. Vanraemdonck, P.S. #24622, Rec. L. 1932, P. 1616, Saginaw County Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3 Sec. Cor., Sec. 4, 5, 8 & 9, T9N-R3E
 Found no evidence of Original Government Corner. Found square iron boat spike in monument box. Verified this iron with record witnesses from 1956-1995 in "A" above. Checked measurements w/1968 Edmond's Survey, E-3 to E-2, R=2633.08, M=2633.14. E-3 East to Edmond's S1/4 Cor. Sec. 4, T9N-R3E R&M=2563.33. Found monument is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3 Sec. Cor., Sec. 4, 5, 8 & 9, T9N-R3E
 Placed 5/8" rerod with "Saginaw County Monument" brass cap stamp P.S. 39096 in existing monument box
 N50°E 99.45' Set N&T 39096 in N. Fce p/p
 S70°E 105.27' Set N&T 39096 in NW Fce p/p
 N30°W 60.11' Fnd N&T 21567 in E Fce p/p
 S45°W 82.98 Fnd N&T 21567 in NW Fce p/p

Signed by John H. Rauser Date Sept 27 1996
 Surveyor's Michigan License No. 39096



MAY 18 1997