

APPROVED BY PEER GROUP P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT

Lib 7 Page 94

SAGINAW COUNTY LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Saginaw Located In: Chesaning Township Corner Code #

Table with 3 columns: Item, T/R/S, R/E/S. Row 1: Public Land Survey, T 9N R 3E, G-5. Row 2: Property Controlling in Section, S T R. Row 3: Miscellaneous Property in Sec., S T R.

RECORDED & FILED SEP 27 3 15 PM 1996 MILDRED N. DODAK REGISTER OF DEEDS SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, John H. Rauser, in a field survey on May 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Cell (4,7) contains a black dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5 Section Corner, Sections 9, 10, 15, & 16, T9N-R3E Wood post placed by J. Mullett, D.S. in 1840 during subdivision of Big Rock Reserve, S62°E 58 lks. (38.28') 7" Elm N87°E 75 lks. (49.50') 9" W. Ash 1878, County survey by H.G. Ives, Deputy County Surveyor. Survey shows corner falls on the Westerly bank of the Shiawassee River. Meander post on N bank of River on N&S Section line (old Poplar remains) @ 7.64 ch. N of corner; also, Meander post on E bank of river on E& W Section line (old W. Oak remains) @ 2.21 ch.E. of corner. 1887, Record plat on "Nason's Addition to the Village of Chesaning" L.1 of maps and plat Pg.77, SCR. By Orville C. Goodale, Surveyor. Makes reference to Section line between Section 9 and 16.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Section Corner, Sections 9, 10, 15, & 16, T9N-R3E Fnd no evidence of Original Government Corner or 1878 County Surveyor Record: Placed corner G-5 on line between F-5 and H-5 (said line agrees closely with measurements shown on the Plat of Nason's Addition as stated in "A" above), at the intersection of a line between G-6 and an iron pipe found at the intersection of Main Street and Brady Street (said pipe is from un-recorded 1977 Spicer Engineering survey. Corner G-5 falls in cultivated field on the Westerly side of the Shiawassee River and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 Section Corner, Sections 9, 10, 15, & 16, T9N-R3E Set 5/8" Re-Rod w/"Saginaw County Monument" Brass Cap, Stamped P.S. 39096, 18' Westerly of Brush Line along Westerly Bank of the Shiawassee River. Buried 3' below grade due to farming activity. A witness iron was placed on the East side of the river on the section line common to Sections 10 and 15, T9N-R3E, as follows from said corner: East, 207.00' Set 1/2" x 3' re-rod w/cap 39096 on Easterly bank of Shiawassee River, west of guard rail on West edge of Corunna Road at the westerly extension of Volkmer Road. N75°E 67.17' Set spike w/tag 39096 NW fce. 18" Ash S75°E 55.20' Set spike w/tag 39096 N fce. 14" Ash S50°E 65.22' Set spike w/tag 39096 W fce 18" Ash

Signed by John H. Rauser Date Sept 23 1996 Surveyor's Michigan License No. 39096



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983 ADAPTED FOR ELECTRONIC PROCESSING MARCH, 1983

MAY 1 8 1997