

APPROVED BY PEER GROUP P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT SAGINAW COUNTY LAND CORNER RECORDATION CERTIFICATE

Lib 7 Page 95

3-13-96 [Signature] Filing Requirement of Act 74, Mich. P.A. 1970

MILDRED M. DODAK REGISTER OF DEEDS SAGINAW COUNTY MICH.

SEP 27 3 15 PM 1986

RECORDED & FILED

Register of Deeds Stamp & File Number

Table with columns: Located In: Saginaw County (County) Chesaning Township; Corner Code #: G-6; and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. Recorded Plat 5. Private Claims

I, John H. Rauser, in a field survey on February 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Cell (6,6) contains a black dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 1/4 Corner, Section 15 & 16, T9N-R3E

Wood post placed by J. Mullett, D.S. in 1840 during Subdivision of Big Rock Reserve S53°E 5 lks. (3.3') 6" W.Oak N68°W 22 lks. (14.52') 7" W.Oak 1851, Plat of the Village of Chesaning L.G.P.561, Andrew Huggins Surveyor 1949, Spicer Engineering field notes, fnd 6" complete tile on end 3.5 feet below gravel surface witnessed and set 3/4" x 20" iron pipe directly above. 1955, unrecorded survey by Spicer Engineering Co. for Henry Haeske 1977, unrecorded survey by Spicer Engineering Co. job no.19227, fnd corner 1977, L.C.R.C by J.W.Martin, P.S. #4699 rec. L.4,P.74 Saginaw Co. Records 1989, Act 132 survey by M.L. Vanraemdonck, P.S.#24622 rec. L.1767,P.59 Saginaw Co. Records 1990, Act 132 survey by M.L. Vanraemdonck, P.S.#24622 rec. L.1775,P.208 Saginaw Co. Records 1990, Act 132 survey by N.C.Caldwell, P.S.#12018 rec. L.1781,P.1161, Saginaw Co. Records 1993, Act 132 survey by M.L. Vanraemdonck, P.S.#24622 rec. L.1873,P.183 Saginaw Co. Records 1994, Act 132 survey by M.L.Vanraemdonck, P.S.#24622 rec. L.1912,P.490 Saginaw Co. Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 1/4 Corner, Section 15 & 16, T9N-R3E

Fnd no evidence of Original Government Survey. Fnd 3/4" pipe in asphalt shoulder 13'± West of C.L of asphalt roadway. Verified pipe with 1949 Spicer Engineering field notes M=106.40' (R=106.43') to SE corner brick house. Found monument also in agreement with more recent records as stated in "A" above and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 1/4 Corner, Section 15 & 16, T9N-R3E

Place 5/8" Re-Rod w/"Saginaw County Monument" Brass Cap Stamped P.S. 39096 and Monument Box S45°W 21.28' Set PK w/tag #39096 SE fce. T/P N45°W 54.86' Set PK w/tag #39096 W fce. T/P S75°E 82.48' Set PK w/tag #39096 S fce U/P N75°E 67.40' Set PK w/tag #39096 S fce. T/P NW 106.40' SE corner brick house (R=106.43')

Signed by [Signature] Date Sept. 23, 1986 Surveyor's Michigan License No. 39096



MAY 1 8 1987