

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW Located in: CHESANING TWP Corner Code #
(County)

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>3E</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1998 OCT -5 A 9:53
 MILDRED H. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY, MI.
 RECORDED/FILED
Liber 7 Page 224
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D Ferguson, in a field survey on AUGUST 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-13 WOOD POST SET BY JOHN MULLETT, DEPUTY SURVEYOR, IN 1840
16" ELM N57°E 12 LINKS
9" ASH S57°W 6 LINKS
NO EVIDENCE OF THIS CORNER REMAINS

SURVEY &
 REMONUMENTATION
 MAR 12 1999
 SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 FOUND 1/2" ROD
LCRC BY SPICER ENG IN 1976 CALLS FOR 1/2" ROD
SCRC WITNESSES IN 1974 CALL FOR 1/2" ROD (ALL WITNESSES GONE)
FIELD NOTES FROM SPICER ENG 1973 SURVEY CALL FOR 199.98 EAST TO G-1, T8N-R3E, MEASURED 200.03'

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX
S15°W 32.39' W LEG OF SIGN
N45°W 42.95' SE COR TELE RISER
S65°E 56.96' STOP SIGN POST
N45°E 70.95' ARROW SIGN POST
EAST 200.03' 3/4" PIPE (G-1, T8N-R3E)

Signed by Brian D Ferguson
Surveyor's Michigan License No. 28454

Date SEPTEMBER 24, 1998

