

BD 9-16-98

SAGINAW COUNTY REMONUMENTATION

LIBER 2084 PAGE 247

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW
(County)

Located in: CHESANING TWP Corner Code # _____

1. Public Land Survey	T <u>9N</u> R <u>3E</u>	<u>H-13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 OCT -5 A 9:53
MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

RECORDED/FILED

Liber 7 Page 225
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D. Ferguson, in a field survey on AUGUST 12, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		6		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13 WOOD POST SET BY JOHN MULLETT, DEPUTY SURVEYOR, IN 1840
7" BEECH S85°E 8 LINKS
14" ASPEN N69°W 24 LINKS
NO EVIDENCE OF THIS CORNER REMAINS

SURVEY &
REMONUMENTATION
MAR 12 1998
SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 FOUND 3/4" PIPE
LCRC BY SPICER ENG IN 1976. SET 3/4" PIPE OVER LARGE FLAT STONE
WITNESS CALLS FOR FENCE RUNNING SOUTH 152 FEET EASTERLY OF CORNER. MEASURED 150.33' TO H-1, T8N-R3E

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX
SOUTH 9.62' SET 1/2" ROD W/CAP 26454
NORTH 27.02' FACE OF TELE RISER
N65°E 40.27' SET NAIL & SHINER E END 14" CMP
N33°W 24.06' SET NAIL & SHINER E END 14" CMP
EAST 150.33' 1/2" ROD (H-1, T8N-R3E)

Signed by Brian D. Ferguson
Surveyor's Michigan License No. 26454

Date SEPTEMBER 24 1998

