

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW Located in: CHESANING TWP Corner Code #
(County)

1. Public Land Survey T 9N R 3E I-13
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

MILDRED H. DODD
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

1999 OCT -5 A 9:53

RECORDED/FILED

Liber 7 Page 226
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D Ferguson, in a field survey on AUGUST 14, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-13 WOOD POST SET BY JOHN MULLETT, DEPUTY SURVEYOR, IN 1840
14" ELM S56°E 11 LINKS AND 5" BEECH N65°W 6 LINKS
CORNER FOUND BY H.CORY IN 1878. 14" ELM S56°E 10 LINKS, 5" BEECH N65°W 6 LINKS
LCRC IN 1979 AND 1988
SURVEY BY ROWE IN 1988
FIELD NOTES FROM 1973 SPICER SURVEY

SURVEY & REMONUMENTATION

MAR 22 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 FOUND 5/8" IRON PIPE
ROWE SURVEY CALLS FOR N40°W, 39.39' TO ROD & CAP 20709. MEASURED N26°W, 39.39'
SPICER NOTES CALL FOR S45°W, 114.3 TO NAIL & ALUM DISC IN PWR POLE. MEASURED 114.15 FEET

SECTION

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX
N26°W 39.39' FOUND ROD W/CAP 20709
S15°W 12.90' E LEG OF SIGN POST
N22°E 51.63' FACE OF SIGN POST
S45°W 114.15' FOUND NAIL & WASHER "ELEV. BENCHMARK, SCRC
N85°E 54.47' FOUND SPIKE W/R.E.I. TAG 39096

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date SEPTEMBER 28, 1998

