

Big 9-16-98

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW Located in: CHESANING TWP Corner Code #
(County)

1. Public Land Survey T 9N R 3E K-13
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Liber 7 Page 227

1998 OCT -5 A 9:53
MILITARY M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.
RECORDED/FILED
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D Ferguson, in a field survey on AUGUST 14, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-13 WOOD POST SET BY JOHN MULLETT, DEPUTY SURVEYOR, IN 1840
20" RED OAK EAST 25 LINKS
9" ASH S68°W 3 1/2 LINKS
LCRC BY VAN RAEMDONCK IN 1996 FROM INFORMATION OBTAINED IN 1978
SURVEYS BY VAN RAEMDONCK IN 1978
SCRC WITNESS SHEET

SURVEY &
REMONUMENTATION
MAY 18 1998
SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-13 FOUND 1/2" ROD W/REI CAP 11192
SCRC WITNESS EAST 40.00' TO SOUTH END 24" CONC DRIVE CULVERT. MEASURED 39.87' TO CHISELED X
SCRC WITNESS N45°E 48.20' TOP CTR NORTH END 24" CONC DRIVE CULVERT. MEASURED 48.45' TO CHISELED X

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP
EAST 39.87' CHISELED X TOP OF S END 24" CONC CULVERT
N45°E 48.45' CHISELED X TOP OF N END 24" CONC CULVERT
N08°E 33.78' CHISELED X TOP OF S END 12" CONC CULVERT
EAST 22.8' ± CTR LINE AMMEN ROAD
S20°E 36.46' SET 1/2" ROD W/CAP 26454

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date _____

