

REMONUMENTATION

MAR 12 1999

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SECTION
SAGINAW COUNTY REMONUMENTATION

LIBER 2084 PAGE 252

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW Located in: MAPLE GROVE TWP Corner Code #
(County)

1. Public Land Survey	T <u>9N</u> R <u>4E</u>	<u>C-13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MIL DRED M. DODDAX
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

1998 OCT -5 A 9:54

RECORDED/FILED

Liber 7 Page 230

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian D Ferguson in a field survey on AUGUST 14, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	9	10	11	12	13	14	15	16	17	18	19	20
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13 WOOD POST SET BY JOHN MULLETT IN 1840
8" SYCAMORE S30°E 6 LINKS
19" ASH N25°E 9 LINKS
NO EVIDENCE OF ORIGINAL CORNER REMAINS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 FOUND ROD W/CAP 12018
AGREES WITH LOCATION IN RECORDED SURVEYS IN SHIAWASSEE COUNTY

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP IN EXISTING MONUMENT BOX
N53°W 36.41' PK & TAG 11192 IN NE COR SPLIT RAIL FENCE POST
S62°E 22.60' 1/2" ROD AT E. END OF CONC., S. SIDE OF DRIVE
N56°E 28.14' 1/2" ROD AT E END OF CONC, N SIDE OF DRIVE
S65°W 28.26' NAIL & SHINER N END 12" CMP
WEST 11.88' C-1, T8N-R4E

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date _____

