

*BD 9-16-98*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Liber 7 Page 232*

For corners in

SAGINAW Located in: MAPLE GROVE TWP Corner Code #  
(County)

1. Public Land Survey T 9N R 4E E-13  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

1998 OCT - 5 A 9: 54  
MILGRED H. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

RECORDED/FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Brian D Ferguson, in a field survey on AUGUST 17, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-13 WOOD POST SET BY JOHN MULLETT, DEPUTY SURVEYOR, IN 1840  
14" SUGAR S16°W 22 LINKS  
13" BEECH N20 1/2°W 9 LINKS  
LCRC BY VAN RAEMDONCK IN 1988  
NO EVIDENCE OF ORIGINAL CORNER REMAINS

SURVEY A  
REMONUMENTATION

SEP 18 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 FOUND 1/2" ROD PER LCRC  
LCRC N60°W 22.78' SE COR ROAD SIGN. MEASURED N54°W 22.58' FACE ROAD SIGN POST  
LCRC N50°W 15.70' N END 24" CULVERT. MEASURED N45°W 15.55' TOP CENTER 24" METAL CULVERT

ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 SET 5/8" STEEL BAR WITH 3" BRASS SAGINAW COUNTY REMONUMENTATION CAP  
N54°W 22.58' FACE ROAD SIGN POST  
N25°E 46.79' FCE STOP SIGN POST  
S18°W 73.19' ROOFING NAIL IN NW FACE PWR POLE  
EAST 16.50' E-1, T8N-R4E  
S28°E 68.89' NW COR TELE RISER

Signed by Brian D Ferguson  
Surveyor's Michigan License No. 26454

Date \_\_\_\_\_

