

**SAGINAW COUNTY REMONUMENTATION 1998
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 2084 PAGE 842

Liber 7 Page 248

or corners in

Saginaw (County)	Located In: Maple Grove Twp	Corner Code #
1. Public Land Survey	T <u>9 N</u> R <u>4 E</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 OCT - 6 A 08
 MILDRED M. DODD
 REGISTER OF DEEDS
 SAGINAW COUNTY MI.
 RECORDED/FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		1		
5													
6	18		17		16		15		14		1		
7													
8	19		20		21		22		23		1		
9													
10	30		29		28		27		26		1		
11													
12	31		32		33		34		35		1		
13													

Ronald C. Prevost, in a field survey on 7-15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13 Post set by D.S. Joseph Wampler 1822±.
 Sugar 8" S.28°W. 6 L.
 Ash 9" N. 1°E. 15 L.
 Ref. by County Surveyor Goodale 1888.
 Act 132 L6, P933 John Rauser #39096 1994 Genesee Co.

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY
[Signature] 9-2-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 No corner found.
 The Co. Surveyors notes "1888" show 40.10 CHS for East 1/2 mile and 39.66 CHS for W 1/2 mile, Totaling 79.76 CHS = 5264.16 for mile.
 Mile measures E-13 to G-13. 5261.74
 $40.10 \div 79.76 = 0.502758$, x 5261.74 = 2645.38 G-13 to F-13.
 $5261.74 - 2645.38 = 2616.36$ (E-13 to F-13).

Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Placed 5/8" bar, Saginaw Co. re-mon cap and mon box at single proportion location described above in Section B. 9/23/98.
 East 17.18' to N 1/4 cor Section 4, T.8 N.-R.4 E.
 N.05°E. 31.03' to pk nail & tag #39096 in E. face wood post next to tel ped.
 S.03°E. 32.52' to pk nail & tag #39096 in E. face wood post next to tel ped.
 S.18°E. 37.28' 1/2" rebar & cap #39096.
 S.35°W. 40.80' face 18" Maple.



Signed by Ronald C. Prevost
 Ronald C. Prevost

Date 9-25-98

Surveyor's Michigan License No. 24612