

**SAGINAW COUNTY REMONUMENTATION 1998
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 2084 PAGE 828

For corners in

<u>Saginaw</u> (County)	Located In: <u>Maple Grove Twp</u>	Corner Code #
1. Public Land Survey	T <u>9 N</u> R <u>4 E</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liberty Page 234

1998 OCT - 6 A 9:08
MILKRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

RECORDED/FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 7-15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-13 Post set by D.S. Joseph Wampler 1822 ±.
Elm 20" N.79°E. 12 L.
Ash 6" N.66°W 30 L.
Spicer Eng. notes 1994
LCRC L1903, P2174 Prevost #24612 3/4" pipe set 1994.

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

RPD 7-29-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13 Found 3/4" pipe at bit surface.
From L1903, P2174 N.40°W. 50.94 center cable pedestal. (50.94M).
From L1903, P2174 S.45°E. 38.35 center cable pedestal (38.35M).
From L1903, P2174 West 8.76 1/2" rod in mon box I-1, T.8 N.-R.4 E. (8.76M).

SURVEY &
REMONUMENTATION
SECTION
OCT 2 1998

Accepted 3/4" pipe as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-13 Replaced 3/4" pipe with 5/8" rod & Saginaw Co. re-mon cap and mon box 9-16-98.
N.40°W. 50.94 ctr cable pedestal.
S.30°E. 38.35 ctr cable pedestal.
West 8.76 1/2" rod in mon box, I-1, T.8 N.-R.4 E.
S.25°W 139.95 face P. pole.



Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-21-98

Surveyor's Michigan License No. 24612