

**SAGINAW COUNTY REMONUMENTATION 1998  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 2084 PAGE 830

For corners in

<u>Saginaw</u> (County)	Located In: Maple Grove Twp	Corner Code # K-13
1. Public Land Survey	T <u>9 N</u> R <u>4 E</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Lib 7 Page 236*

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

1998 OCT - 6 A 9:08

RECORDED/FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ronald C. Prevost, in a field survey on 7-15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11			
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35			
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-13 Post set by D.S. Joseph Wampler 1822+.  
Beech 12" S.55° E. 10 L.  
Cherry 9" N.89° W.19 L.  
LCRC L3, P56, Piotrowski #9685 1974 1/2" re-rod found.  
Spicer Notes of 1994 found 1/2" re-rod bent, replaced with 3/4" pipe, 1994.

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

*RD* 7-29-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Found 3/4" pipe.  
From L3, P56 P.P. N.40°E. 58' (58.04M fnd nail & washer #39096 SE face).  
From L3, P56 West 19.34 NW cor Sec. 1, Hazelton Twp. (19.35M).

SURVEY &  
REMONUMENTATION

MAR 12 1999

Accepted as the best available evidence of the position of the original corner.

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Replaced 3/4" pipe with 5/8" bar & Saginaw Co re-mon cap 6" below gravel 9-16-98.  
N.50°E. 58.04 fnd nail & washer #39096 in SE. face P.pole.  
S.22°E. 115.75 fnd nail & washer #39096 in SE. face P.pole.  
S.23°W. 109.05 fnd nail & washer #39096 in E. face P. pole.  
West 19.35 NW corner Sec. 1, T.8 N.-R.4 E.  
East 33.00 3/4" pipe w/cap #41115.



Signed by

*Ronald C. Prevost*

Date

9-21-98

Ronald C. Prevost

Surveyor's Michigan License No. 24612