

**SAGINAW COUNTY REMONUMENTATION 1998  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER **2084** PAGE **829**

For corners in

<u>Saginaw</u> <small>(County)</small>	Located In: <u>Maple Grove Twp</u>	Corner Code #
1. Public Land Survey	T <u>9 N</u> R <u>4 E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 OCT -6 A 9:08  
 MILDRED M. DODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY, MI.  
**RECORDED/FILED**  
*Liber 7 Page 235*  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Ronald C. Prevost, in a field survey on 7-21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

L-13 Post set by D.S. Joseph Wampler 1822±  
 Sugar 14" S.39"E. 25L.  
 Beech 9" N.25"W. 19L.  
 LCRC L3, P56 Piotrowski #9685 1924 1/2" Re-rod set.

APPROVED BY PEER GROUP  
 P.A. 345 OF 1990  
 SAGINAW COUNTY

*RDJ* 7-29-98

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-13 Found 1/2" Re-rod 0.4' below gravel.  
 From L3, P56 West 9.67 N 1/4 cor Sec. 1, T.8 N.-R.4 E. (9.57M).  
 From L3, P56 S.10"W. 26.63 A. Post (26.95 ctr. anchor post).  
 From L3, P56 S.55"E. 40.85 32" bass (41.04 set nail in N. face 10" Basswood after growth).

SURVEY &  
 REMONUMENTATION

MAR 13 1999

Accepted as the best available evidence of the position of the original corner.

SECTION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-13 Replaced 1/2" rod with 5/8" rod with Saginaw Co. Re-mon cap 6"± below gravel 9-16-98.  
 S.55"E. 41.04 set nail in N. Face 10" Basswood.  
 N.84"E. 103.16 center Tel. pedestal.  
 S.27"W. 26.57 center anchor post.  
 S.68"W. 39.90 set nail N. face 12" Ash.  
 West 9.57 N. 1/4 cor Sec. 1, T.8 N.-R.4 E.



Signed by Ronald C. Prevost  
 Ronald C. Prevost

Date 9-21-98

Surveyor's Michigan License No. 24612