

1999

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SECTION

LIBER 2084 PAGE 223

SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MIL DRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

1998 OCT -5 A 9:48

RECORDED/FILED

Lib 7 Page 201

Register of Deeds Stamp & File Number

For corners in

SAGINAW COUNTY

(County)

Located In: **MAPLE GROVE**
Corner Code #

- 1. Public Land Survey T 9N R 4E M-2
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JUNE 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-2

- 1. POST SET BY JOSEPH WAMPLER, D.S., NO DATE GIVEN.
11" ELM N65°W 17 LINKS; 17" ELM S85°E, 12 LINKS.
- 2. LCRC RECORDED L.1, P.6, A. LEACH, PS#7236, (1971), FOUND 1" AXLE SHAFT IN MONUMENT BOX.
- 3. CERTIFICATE OF SURVEY L. 1338, P. 619 A. LEACH PS#7236, (1971), 1" SHAFT WITH 3" COG WHEEL.
- 4. CERTIFICATE OF SURVEY L.1435, P.1138, A. LEACH, PS#7236, (1974), FOUND 1" AXLE SHAFT.
- 5. CERTIFICATE OF SURVEY L.1872, P.2124, B. FERGUSON, PS#26454, (1993), FOUND PK NAIL AND RESET RAILROAD SPIKE (1993).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2

SEARCHED APPARENT LOCATION OF THE CORNER AND FOUND A RAILROAD SPIKE.
CHECKED WITNESSES ON SURVEY L. 1872, P.2124 N40°E TO NAIL IN NORTHWEST FACE OF 18" MAPLE 68.0' (R) 67.97'(M); N70°E TO NAIL IN NORTHWEST FACE OF 36" MAPLE 52.9' (R) 52.85'(M)
CHECKED WITNESSES IN LCRC L. 1, P. 6 EAST TO SPIKE & MSHD CAP IN POWER POLE 65.2' (R&M).
ACCEPTED RAILROAD SPIKE AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2

REPLACED RAILROAD SPIKE WITH 5/8" X 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP IN MONUMENT BOX.
WEST 1.7' TO THE PHYSICAL CENTERLINE OF HIGHWAY M-13.
N30°E 67.97' TO NAIL IN NORTHWEST FACE OF 18" MAPLE.
N62°E 52.85' TO NAIL IN NORTHERLY FACE OF 36" MAPLE.
S30°E 127.20' TO CHISELED "X" ON TOP OF R/W MARKER.
N48°W 83.45' SET NAIL AND TAG IN NORTHEAST FACE OF 12" PINE.
EAST 65.20' TO A FOUND SPIKE AND MSHD TAG IN POWER POLE.

Signed by Dale Winiecke

Date 3/30/99

Surveyor's Michigan License No. 41915

