

MAR 2 1999

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

LIBER 2084 PAGE 224

SECTION
SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SAGINAW COUNTY

(County)

Located In: **MAPLE GROVE**

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T <u>9N</u> R <u>4E</u> | M-3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED/FILED

1998 OCT -5 A 9:48

MILFRED N. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

Lib 7 Page 209

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JUNE 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- M-3
- POST SET BY JOSEPH WAMPLER, D.S., NO DATE GIVEN. 6" BEECH, S 38°2, 13 LINKS; 14" BEECH, N20°E, 16 LINKS.
 - LCRC L.1, P.6, A. LEACH, PS#7236, (1971) FOUND 1" IRON IN MONUMENT BOX.
 - CERTIFICATE OF SURVEY 1338, P.619 A. LEACH PS#7236 (1971), 1" PIPE.
 - CERTIFICATE OF SURVEY L.1381, P.1053, 1054, 1056, F. SHALTZ, JR., PS#13595 (1972), NO WITNESSES.
 - CERTIFICATE OF SURVEY L.1435, P.1138, A. LEACH, PS#7236 (1974), FOUND 1" ROD IN MONUMENT BOX.
 - CERTIFICATE OF SURVEY L.1431, P.224, B. GRIGGS, JR., PS#14763, (1979), FOUND MONUMENT BOX.
 - LCRC RECORDED IN L.4, P.219, B. GRIGGS, JR., PS#14763, (1979), FOUND 1/2" ROD IN MONUMENT BOX.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3
SEARCHED APPARENT LOCATION OF CORNER AND FOUND MONUMENT BOX WITH 1" PIPE. EXCAVATED AREA UNDER 1" PIPE AND FOUND BOAT SPIKE 2' BELOW ROAD SURFACE.
CHECKED WITNESSES FROM LCRC L.4, P.219 AND SURVEY L. 1431, P.224 N60°E TO CORNER OF FOUNDATION HOUSE #12842 85.02' (R&M); S10°W TO NORTHWEST CORNER OF CONCRETE HEADWALL 72.85' (R&M); N45°W TO NAIL IN UTILITY POLE 69.45' (R&M); SOUTH TO MONUMENT BOX NORTHWEST CORNER SEC 7 T9N, R5E 53.65' (R) 53.69' (M).
CHECKED WITNESSES ON SURVEY L1338, P. 619 N57°W TO STREET SIGN 62.4' (R) 61.6' (M).
ACCEPTED 1" PIPE IN MONUMENT BOX AS BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3
REPLACED 1" PIPE IN MONUMENT BOX WITH 5/8" X 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP.
EAST 2.65' TO PHYSICAL CENTERLINE HIGHWAY M-13.
SOUTH 1.1' TO PHYSICAL CENTERLINE CHESANING ROAD.
N62°E 94.73' TO NORTHWEST CORNER BLOCK FOUNDATION.
S37°E 108.18' TO CENTERLINE CONCRETE R/W MARKER.
S66°W 46.23' TO SOUTHEAST CORNER CONCRETE HEADWALL.
N54°W 69.79' TO NAIL/TAG IN POWER POLE.
SOUTH 53.69' TO A-3, T9N, R5E, GENESEE COUNTY REMONUMENTATION CORNER.

Signed by Dale Winiecke

Date 9/30/98

Surveyor's Michigan License No. 41915

