

MAR 28 1999

LIBER 2084 PAGE 225

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SECTION

SAGINAW COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

304 9-2-98

For corners in

SAGINAW COUNTY
(County)

Located In: MAPLE GROVE
Corner Code #

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>9N</u> R <u>4E</u> | <u>M-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

MILCREED M. DODDAR
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

1998 OCT -5 A 9:48

RECORDED/FILED

Liber 7 Page 203

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JUNE 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-4
- POST SET BY JOSEPH WAMPLER, D.S., NO DATE GIVEN.
36" WHITE OAK, S 89°E, 17 LINKS; 9" BEECH, S30°W, 23 LINKS.
 - LCRC RECORDED IN L.2, P.243, J. MARTIN, PS#4699, (1974), MONUMENT BOX WITH 5/8" REROD.
 - CERTIFICATE OF SURVEY, L.1924, P.897, M. VANRAEMDONCK, PS#24622, (1992), FOUND IRON PIN IN MONUMENT BOX.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4

SEARCHED APPARENT LOCATION OF CORNER AND FOUND 3/4" BAR IN MONUMENT BOX. EXCAVATED UNDER BOX AND FOUND 1" REBAR 2.5' UNDER 3/4" BAR.
CHECKED WITNESSES ON LCRC L. 2, P.243 SOUTHWEST TO NAIL AND CAP IN TELEPHONE POLE 142.91'(R) 142.63'(M); SOUTHEAST TO NAIL AND CAP IN POWER POLE 126.40'(R&M)
CHECKED WITNESSES ON SURVEY L. 1924, P. 898 N70°E TO NAIL & TAG IN SOUTH FACE 14" ELM 48.57'(R) 48.81'(M); N50°E TO NAIL & TAG IN UTILITY POLE 86.40'(R&M); SOUTH TO IRON PIN IN MONUMENT BOX 34.84'(R) 34.78'(M).
ACCEPTED 1" BAR UNDER 3/4" BAR AS BEST AVAILABLE EVIDENCE OF ORIGINAL CORNER LOCATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4

REPLACED 3/4" BAR IN MONUMENT BOX WITH 5/8" X 24" REROD WITH SAGINAW COUNTY REMONUMENTATION CAP.
WEST 1.2' TO PHYSICAL CENTERLINE HIGHWAY M-13
S39°E 126.47' TO SET NAIL/TAG IN NORTHWEST FACE OF POWER POLE.
N46°E 86.88' TO SET NAIL/TAG IN NORTHWEST FACE OF POWER POLE.
N 27°W 122.15' SET NAIL/TAG IN EAST FACE OF 12" MAPLE.
S62°E 59.22' TO CHISELED 'X' IN NORTH END 24" LONG PIPE.
N58°W 70.32' TO SET CHISELED 'X' TOP OF R/W MARKER.

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 9/30/98

