

**SAGINAW COUNTY REMONUMENTATION 1998  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER **2084** PAGE **838**

For corners in

<u>Saginaw</u> (County)	Located In: <b>Maple Grove Twp</b>	Corner Code # <b>M-7</b>
1. Public Land Survey	T <u>9 N</u> R <u>4 E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

RECORDED/FILED  
1998 OCT -6 A 9:08  
MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.  
*Liber 7 Page 244*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claim§ \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Ronald C. Prevost, in a field survey on 7-23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M7 Post set by D.S. Joseph Wampler 1822±.  
Lynn " S.45°E. 18 L.  
Ironwood 4" N.51°W. 13 L.  
Shown on M.D.O.T. R/W plans 1937± M-13 & M-57.  
LCRC L1, P242, J. Martin 1972 mon/box 5" iron.  
Act 132 L1920, P1811-14 by John Rauser P.S. #39096 1994, Axel shaft/mon box.

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY  
*BDP B-5-98*  
SURVEY & REMONUMENTATION

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-7 Found 4" iron in mon box.  
From L1, P242 NW 81.57 face P. pole. (82.07M nail & tag SW face P. pole).  
From L1, P242 SW 80.73 face P. pole. (80.82M nail & tag #39096 N face traffic signal pole).  
From L1, P242 NE 68.40 face P. pole. (68.27M lag bolt W face traffic signal pole).  
From Act 132 L1920, P1811-14, N.60°E. 68.33 P.K. SW face traf L/P (68.27 lag bolt W face traffic pole).  
From Act 132 L1920, P1811-14, S.66°E. 150.48 P.K. & tag #39096 SW face P. pole. (149.63 N&T #39096 SW face P.P.)

OCT 2 1998  
SECTION

Accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-7 Replaced Iron in mon box described above with Saginaw Co re-mon cap & 5/8" rod in existing mon box 9-23-98.  
N.65°E. 68.27 lag bolt in W face traffic signal pole.  
S.65°E. 149.63 nail & tag #39096 SW face P. pole.  
S.50°W. 80.82 P.K. nail & tag #39096 N face traffic signal pole.  
N.50°W. 82.07 nail & MSHD tag SW face P. pole.  
East 1.5 physical ⚡, M-13.  
North 0.0 physical ⚡, M-57.



Signed by Ronald C. Prevost  
Ronald C. Prevost

Date 9-25-98

Surveyor's Michigan License No. 24612