

**SAGINAW COUNTY REMONUMENTATION 1998  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 2084 PAGE 833

corners in \_\_\_\_\_

<u>Saginaw</u> (County)	Located In: <u>Maple Grove Twp</u>	Corner Code # <u>M-8</u>
Public Land Survey	T <u>9 N</u> R <u>4 E</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

*Lib 7 Page 239*

1998 OCT - 6 A 9:08  
MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

RECORDED/FILED

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

Ronald C. Prevost, in a field survey on 7-23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, covered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	1						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

M-8 Post set by D.S. Joseph Wampler 1822+.  
Ash 18" N.85°W. 7 1/2 L.  
Lynn 11" S.35°E. 26 L.  
Approx location shown on M.D.O.T. r/w plans 1937+.  
LCRC L1756, P2132, Paul Brown #33134, 1989, set P.K. & disc. #11192 from info on survey by E. McCombs/1974 Co. Pwr. Co. job

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

*Blair* 7-29-98

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found P.K. & tag #11192  
From L.C.R.C. L1756, P2132 N.40°E. 79.98 tag #11192 SE face P/P (79.95M)  
From L.C.R.C. L1756, P2132 S.85°W. 65.93 tag #11192 N face T/P (65.93M).  
From L.C.R.C. L1756, P2132 S.50°E 58.08 fnd. property iron #11192(58.08M).  
From L.C.R.C. L1756, P2132 North 10.88 P.K. & tag #11192 W 1/4 cor. Sec. 9, T.9 N.-R.5 E. (10.87M)

SURVEY &  
REMONUMENTATION


2007 8 3099

SECTION

Accepted as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Set mon box with 5/8" rod Saginaw Co. re-mon cap in place of P.K. found 9-17-98.  
N.60°E. 79.95 nail & tag #11192 SE face P. pole.  
S.55°E. 50.08 1/2" prop cor. w/cap #11192.  
S.85°W 65.93 nail & tag #11192 N. face T. pole.  
North 10.87 W 1/4 post Sec 19, T.9 N.-R.5 E. P.K. & tag #11192.



signed by Ronald C. Prevost  
Ronald C. Prevost

Date 9-21-98

Surveyor's Michigan License No. 24612