

**SAGINAW COUNTY REMONUMENTATION 1998
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

LIBER **2084** PAGE **837**

<u>Saginaw</u> (County)	Located In: <u>Maple Grove Twp</u>	Corner Code #
1. Public Land Survey	T <u>9 N</u> R <u>4 E</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1998 OCT -6 A 9:08
 MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY, MICH.
 RECORDED/FILED
Libe *Pages 43*
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 7-21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11			
5													
6		18		17		16		15		14			
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26			
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 Post set by D.S. Joseph Wampler 1822±.
 Sugar 7" N.4°E. 24 L.
 Sugar 8" S.4°W. 9 L.
 Shown on M.D.O.T. plans 1937±.
 L.C.R.C. L1638, P1157 VanRaemdonck #24622 set conc. nail & washer 60' East of conc r/w marker, using info from Act 132 L1353, P933 John Budzik #18082 (60' East of 4" pipe).
 Act 132 L1638, P1154 VanRaemdonck #24622 (60' East of conc. r/w marker).

SURVEY &
REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found P.K. nail, agrees with 2 witnesses from L1638, P1157 & L1638, P1154.
 Also found 1/2" rod in mon box S.10°W. 2.19 from P.K. nail.
 Distance South from 1/2" rod in mon box to corner M-13 = 2638.69 (r/w maps 2638.4).
 Distance North from 1/2" rod in mon box to corner M-11 = 2625.31 (r/w maps 2625.25).

MAR 2 1999

SECTION

1/2" rod in M.B. accepted as the best evidence of original position of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Placed 5/8" bar and Saginaw Co re-mon cap in existing mon box 9-17-98.
 S.80°E. 60.00 top center conc. r/w marker.
 S.23°E 85.20 N. end 12" CMP.
 N.80°W. 58.16 top center tel pedestal.
 N.40°W. 62.50 N. end 12" CMP.
 East 2.85 const to M-13.
 N.10°E. 2.19 P.K. nail & washer.

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY
BDP 8-5-98



Signed by Ronald C. Prevost
 Ronald C. Prevost

Date 9-21-98

Surveyor's Michigan License No. 24612