

APPROVED BY PEER GROUP FOR SAGINAW COUNTY REMONUMENTATION 1999  
 P.A. 345 OF 1990 LAND CORNER RECORDATION CERTIFICATE  
 SAGINAW COUNTY Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED & FILED

SEP 28 3 16 PM '99

For corners in

MILDRED A.  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.

LIBER 2144 PAGE 743

*Sheet 8 Page 15*  
 Register of Deeds Stamp & File Number

Saginaw (County) Located In: Brant Twp. Corner Code #

1. Public Land Survey T 10N R 2E C-5  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

4. Lot No. , Recorded Plat  
 5. Private Claims

I, Roger P. Mahoney, in a field survey on 9-23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5 Post set by Wm. Brookfield P.S. 1824.  
 Pine 30° N. 9°W. 26 Lks.  
 Maple 10° S. 21°W. 25 Lks.  
 LCRC L4 P49, 1977, Prevost fnd Pine root & stones set 1 1/4" x 18" iron bar.  
 LCRC L5 P48, 3/4" pipe set 1976 recorded 1980.

SURVEY &  
 RE-MONUMENTATION

MAR 09 2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SECTION

C-5 Found 1 1/2" x 18" iron bar 18" below gravel surface.  
 In survey work by Spicer Eng. in 1977 found the Pine root & stones as per notes by John Teft's notes of 1910 and set 1 1/4" x 18" iron bar over stones and pine root.  
 Also found 3/4" pipe as set by D. Hammond in 1976 but not recorded until 1980. Hammond's 3/4" pipe is 14.1± West & 2' ± South of John Teft's corner.

Accepted 1 1/2" x 18" iron bar as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 Replaced 1 1/2" x 18" iron bar with 5/8" rod and Saginaw County Re-mon cap stamped #24612.  
 N.05°E. 26.36' nail & tag in W. face Cedar post; (Recorded 26.02' LCRC Prevost).  
 N.25°E. 97.53' nail & tag in SE face abandoned utility pole. (recorded 97.37 LCRC Prevost).  
 S.30°W. 88.75' set nail & tag in NW face 30" Elm (recorded 88.21 LCRC Prevost).  
 N.30°W. 29.95' set nail & tag in NE face 10" wood fence post.



Signed by Roger P. Mahoney  
 Roger P. Mahoney  
 Surveyor's Michigan License No. 41105

Date \_\_\_\_\_