

SURVEY & REMONUMENTATION

MAR 18 1998

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE RECORDED & FILED
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION Township

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>5E</u>	<u>B-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 4-29, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13 Post set by J. Wampler about 1822.
Ash 7 in S.25E. 10L.
Elm 11 in West 30 L.
Spicer notes 1969, No point found, corner determined 2188.70 E. of A-13.
Spicer notes 1976, 1 3/8"x24" pipe set at above determined location.
L.C.R.C. L2 P21, Leach 1972 set t-iron, witnesses gone.
Act 132, L1390 P1183 & L1452 P932 Kelly-Leach refer Leach t-iron.
Act 132, L1555 P372, L1587 P2187, L1667 P219, L1668 P2289, all by Leach.
Refer 1 1/2" pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 Found 5/8" re-bar at location of previous 1 3/8" pipe, also found t-iron from L.C.R.C. L2 P21, 4-29-97 which stands 7.6'W. & 1.2' S of 5/8" bar. Upon searching at single proportion location found t-iron 35.5' ± E. & 2.2' ± N. of 5/8" bar 9-9-97. Single proportion distance between A-13 & C-13 falls 2225.17 East of A-13 t-iron found is 2224.48' E. of A-13 and 1.0' ± S. of line A-13-C-13.
Peer Group approved t-iron location as found (9-18-97).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 Replaced t-iron with 5/8" re-rod, Saginaw Co. re-mon cap & mon box 9-25-97.
S.03°E. 37.20 nail & cap W. side 14" Ash.
S.02°W. 37.31 nail & cap E. side 18" Oak.
S.10°W. 39.89 nail & cap E. side 8" Oak.
N.02°W. 36.65 nail & cap SE. side 12" Oak.

Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612

SEP 25 3 23 PM '97

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 93

Liber 7 Page 133

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

9-18-97 *[Signature]*

