

**SAGINAW COUNTY RE-MON 1997  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED & FILED**

For corners in Taymouth Township

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>5E</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SEP 25 9 23 PM '97**

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 91

*Liber 7 Page 131*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ronald C. Prevost, in a field survey on 5-6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

D-13 Post set by J. Wampler about 1822.  
Beech 20" N.84E. 21L  
Beech 23" S.66W. 20L  
L.C.R.C. L4-P184, Leach, 1978, 3/4" bar/mon box (recorded in error, this is post on West line of Reserve).

**SURVEY & REMONUMENTATION**

MAR 18 1998

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

D-13 Temp. nail set on line of E-13 & res. cor. extended at 81.47' West of Reserved corner, location approved by Peer Group on 8-28-97.  
Note: The G.L.O. distance is 1.23 chains = 81.18 feet.  
20  
 $36.77 \times 2568.10 = 1324.787, 1324.787 \times 2 = 2649.574, 2649.574 - 2568.10 = 81.474$

**SECTION**

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

*RD 8-28-97*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-13 Set 5/8" re-rod, Sag. Co. cap and mon box, 9-9-97.  
East 81.47 3/4" bar in m box, res. cor.  
N.65°E. 58.05 nail & cap S. side p. pole stub.  
N.10°E. 29.80 nail & cap E. side 12" Pine.  
N.25°W. 75.29 nail & cap E. side p. pole.  
N.60°W. 66.61 nail & cap E. side 15" Pine.



Signed by Ronald C. Prevost  
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612