

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED & FILED

For corners in Taymouth Township

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>5E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 4-30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 Post set by J. Wampler about 1822.
Pine 32" S.73 1/2°E. 127 L
Pine 30" S.18°E. 107 L
L.C.R.C. L1-P256, Martin, 1972 3/4" pipe.
L.C.R.C. L4-P2, Tommer, 1976 3/4" pipe in mon box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found 3/4" pipe in mon box 4-30-97.
L1-P256, S.36.55 nail W. face 20" Oak (M 36.40)
L1-P256, NE 53.35 to face 18" Pine (M 53.58 to nail S face)
L4-P2, S.36.40 nail & tag W edge 12" Oak (M 36.40)
Approved by Peer Group 8-28-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Replaced 3/4" pipe with 5/8" re-rod, Sag. Co. cap in ex. mon box 9-9-97.
South 36.40 nail & tag W. side 20" Oak.
N.40°E. 53.58 nail S face 18" Pine.
N.40°W. 34.91 nail & cap E. side 18" Pine.
N.05°W. 29.15 nail & cap E. side 18" Pine.

Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612

SEP 25 9 23 PM 1997

**MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.**

LIBER 2027 PAGE 90

Liber 7 Page 130
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY**

8-28-97 BDF

**SURVEY &
REMONUMENTATION**

MAR 18 1998

SECTION

