

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED & FILED

For corners in Taymouth Township

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 5E	F-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Sep 25 3 23 PM '97

MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 88

Liber 7 Page 128

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY & REMONUMENTATION

MAR 18 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

F-13 Post set by J. Wampler about 1822.
Elm 9° S.43E. 15 L
Lynn 8° N.85W 12 L
L.C.R.C. L4 P2, Tommer, 1976, T-iron set sing. prop E-13/G-13
Act 132 L1491 P976, Tommer
Act 132 L2005 P363, Snyder

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found T-iron W/cap #22444, Tommer.
L4 P2 N.5°W. 29.50 12" Elm, (M 30.14 to face 18" Cottonwood)
L4 P2 West 22.90 face 18" Oak (M 23.5 to face 18" Wild Cherry)
Current field work supports the single prop. in L.C.R.C. above.
Approved by Peer Group 8-28-97.

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

8-28-97 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Replaced T-iron with 5/8" re-rod, Sag. Co. cap, 9-9-97 in 2"x30" steel pipe filled conc.
N.5°W. 30.14 set nail E side 18" Cottonwood.
West 23.88 set nail N side 18" Wild Cherry.
N.45°W. 9.80 set nail E side 6" Maple.
N.45°E. 8.02 set nail SE side 6" Ash.
South 14' & ditch.



Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612