

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE : RECORDED & FILED
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Taymouth Township

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 5E	I-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	R _____
	S _____ T _____	R _____
3. Miscellaneous Property in Sec.	S _____ T _____	R _____
	S _____ T _____	R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 Post set by J. Wampler about 1822.
Sugar 5 in. S.12 1/2°W. 18 L
Lynn 16 in. East 5 L
L.C.R.C. L1 Pg 79, Leach, 1971. Set t-iron & cap.
Act 132 L1343 P1052, Leach, 1971, t-iron & cap.
Act 132 L1398 P626 Rowe, 1973, pt. not identified.
Spicer Eng. notes of 1967 found 3/4" □ iron, no witnesses.
Spicer Eng. notes of 1977 found 3/4" □ iron, witness gone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found 3/4" □ iron, t-iron from above stands 6.2'E. & 0.7'N.
Peer Group approved 3/4" □ bar location on 8-28-97.
During excavation for mon box found large pointed stone directly below 5/8" □ iron bar 9-17-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Replaced 3/4" □ bar with 5/8" re-rod, Sag. Co. re-mon cap. Set mon box 9-17-97.
N.05°W. 28.37 E. edge stop sign.
S.15°E. 21.48 E. edge E. leg of arrow sign.
S.10°E. 20.54 W. edge W. leg of arrow sign.
East 152.14 3/4" pipe (I-1 T.9 N.-R.5 E.)

SEP 25 9 23 PM '97

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 86

Sheet 7 Page 126
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY
8-28-97 [Signature]

SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION



Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612