

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE, RECORDED & FILED
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Taymouth Township

<u>Saginaw</u>	Located In:	Corner Code
# _____		
(County)		
1. Public Land Survey	T <u>10N</u> R <u>5E</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SEP 25 3 23 PM '97

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 85

Lib 7 Page 125

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on 5-6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 Post set by J. Wampler about 1822.
Hickory 20 in. S.9°W. 11 L
Lynn 36 in. N.4°W. 11 L
County Surveyor H. Cary, 1879, Notes indicate corner on line & mid-way between I-13 & K-13, 40.04 CHS/2642.64.
L.C.R.C. L1-Pg 79, Leach, 1971, t-iron & cap set.
Act 132 L1343 P1052 Leach, 1971
Act 132 L1398 P626, Rowe, 1973

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found t-iron in mon box 5-6-97. Not on line, not at single proportion between I-13 & K-13, dug at single proportion location and found large flat stone with no distinct point. Single proportion location falls in approximate center of stone.
Peer Group approved single proportion location between I-13 & K-13, 6-26-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Remove stone, set 5/8" re-rod, re-mon cap and mon box.
T-iron in mon box stands 0.55'E & 1.05N 7-2-97.
S.45°E. 124.12 nail & cap N. side p pole.
N.75°W. 50.41 nail & cap E side 24" Ash.
North 73.28 nail & cap E side 18" Wild Cherry.
N.45°E. 216.38 SW cor. fnd'n house.

Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY
6-26-97
SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION

