

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED & FILED

SEP 25 3 23 PM '97

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 83

Liber 7 Page 123
Register of Deeds Stamp & File Number

For corners in Taymouth Township

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 5E	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-13 Post set by J. Wampler about 1822.
Maple 16 in S.45E. 15 L
Beech 13 in N.30W. 2 1/2 L
L.C.R.C. L4 P37, D. Rowe 1977, t-iron set.
L.C.R.C. L4 P214, J. Martin 1979 1" iron bar set.
Spicer notes of 1972, observed fence to N. at 2651' W of M-13.
Spicer notes of 1974, dug at 2651' W. of M-13 found nothing, set 1" iron bar on line between K-13 & (L-1 T.9 N.-R.5 E.) and 66.00' West of said L-1 T.9 N.-R.5 E., measured East 2650.82 to M-13, previously 2651'

**SURVEY &
REMONUMENTATION**

MAR 18 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found 1" iron bar L4 P214.
Dug hole mid-way between K-13 & M-13 found t-iron 1.0' below gravel surface.
Apparently Rowe t-iron. L4 P37.
Peer Group approved 1" bar location 8-28-97.

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

8-28-97 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Replaced 1" iron bar with 5/8" re-rod, Sag. Co. re-mon cap & mon box 9-17-97.
N.70°W. 69.57 nail & cap NE. side 30" Oak.
North 30.52 nail & cap E. side 16" Elm.
S.70°E. 68.45 nail & cap N. side 36" Oak.
N.70°E. 86.59 nail & cap S. side 12" Apple.
East 66.08 1/2" iron bar L-1 (T.9 N.-R.5 E.)



Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612