

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE** RECORDED & FILED
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Taymouth Township

Sep 25 3 23 PM '97

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 82

Liber 7 Page 122

Register of Deeds Stamp & File Number

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>5E</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-13 Post set by J. Wampler about 1822.
Beech 8 in N.30E. 17 L
Beech 18 in S.82W. 21 L
Spicer Eng. notes 1968, mon box.
Spicer Eng. notes 1972, mon box empty.
Spicer Eng. notes 1973, pointed stone/mon box.
Spicer Eng. notes 1974, mon box.
Spicer Eng. notes 1987, pointed stone/ mon box
L.C.R.C. L2 P226, J. Martin, Pt of stone in mon box, recorded as A-11, but I believe it to be M-13.

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

6-26-97 

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Found large pointed stone in mon box 5-6-97.
Distances measured West check with previous Spicer distances.
Recovered one witness from L2 P226 (SE 102.3 face p. pole 102.37 M)
Peer Group approved pointed stone in mon box 6-26-97.

**SURVEY &
REMONUMENTATION**

MAR 18 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Drilled hole 5/8" x 10" deep into stone, set 5/8" re-rod into hole.
Set Sag. Co. re-mon cap & placed concrete around stone & inside mon box. 7-1-97.
S.40°E. 102.37 nail & tag W. side P. pole.
S.10°W. 76.38 E. edge Gen. Co. enter sign.
N.40°E. 66.19 nail & cap S. side 12" Maple.



Signed by 
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612