

SAGINAW COUNTY RE-MON 1997 RECORDED & FILED
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SEP 25 3 25 PM '97

For corners in Birch Run Township

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>Saginaw</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>10N</u> R <u>6E</u> | <u>B-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 98

Liber 7 Page 138

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-7, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | I |
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13 Post set by J. Wampler 1822.
Lynn 18 in N.52W. 15 L
Beech 7 in S.49 1/2 E. 26 L
L.C.R.C. L4 P178, Leach 1978 Found 3/8" rod.

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

8-28-97 RDA

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 Found 1/2" re-rod 5-7-97 recorded by Leach L4 P178 recovered one witness S.5°E. 44.00 nail in NE'y stem Elm clump (M 44.13) Measurement East 2650.13 agrees ± with Leach measurement in Act 132 L1552 P235 2650.26
Single proportion location between A-13 & C-13 falls 11'± East of recorded 1/2" rod. Found nothing at sing. prop. location
Peer Group approved 1/2" rod location as recorded by Leach L4 P178, 8-28-97
During excavation for mon box found 8" dia. stone and broken hook from log chain around 1/2" rod. 9-17-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 Replaced 1/2 rod with 5/8 re-rod, Sag Co. Remon cap & mon box 9-17-97.
S.05°E. 44.13 Nail & Ribbon N. side clump 7-8" Ash.
N.30°W. 55.56 Nail & Cap E side 12" Elm.
N.10°W. 64.59 Nail & Cap E side 14" Pine.
N.05°E. 104.28 Nail & Cap S. side 24" Hickory.



Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612
SURVEY & REMONUMENTATION

MAR 18 1998

SECTION