

**SAGINAW COUNTY RE-MON 1997  
LAND CORNER RECORDATION CERTIFICATE RECORDED & FILED  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **Birch Run Township**

<u>Saginaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>6E</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Sep 25 9 25 PM '97**  
 MILDRED M. DODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.  
 LIBER 2027 PAGE 97  
*Sheet 7 Page 137*  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Ronald C. Prevost, in a field survey on 5-7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-13 Post set by J. Wampler 1822.  
 Beech 14 in N.20E. 17 L  
 Beech 18 in S.8 W. 4 L  
 Spicer notes of 1973, fnd 3/4" pipe  
 Spicer notes of 1974, fnd 3/4" pipe  
 L.C.R.C. L4 P 178 Leach, 1978 3/4" pipe found.

APPROVED BY PEER GROUP  
 P.A. 345 OF 1990  
 SAGINAW COUNTY  
*6-26-97 RCP*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found 3/4" pipe.  
 Recovered one witness from L4 P178, S.3°W 27.80 P.K. face 30" Catalpa (27.8 M)  
 Recovered one witness from Spicer Eng. notes 1973. South 27.80 face 20" Catalpa (27.8 M)  
 Approved by Peer Group 6-26-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 Replaced 3/4" pipe with 5/8" Re-rod Sag. Co. Re-mon cap & mon box  
 6" below gravel 7-1-97.  
 South 28.97 nail & R.L.S. cap E side 30" Catalpa stump.  
 S.10°E. 32.25 nail & R.L.S. cap E. side util. pole.  
 S.45°E. 83.95 nail & cap SW side Elm.  
 N.45°W. 63.92 nail & cap E side 10" Apple.



Signed by Ronald C. Prevost  
 Surveyor's Michigan License No. 24612

Date 9-25-97

MAR 18 1998

SECTION