

SURVEY & REMONUMENTATION

MAR 18 1998

**SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE** RECORDED & FILED
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in Birch Run Township

Saginaw (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>6E</u>	<u>D-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SEP 25 3 25 PM '97

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 96

Liber 7 Page 136

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 5-7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 Post set by J. Wampler, 1822.
Sugar 10 inc S.63 E. 24 L
Sugar 11 in S.81 W. 26 L
Spicer Eng. notes 1973, observed fence to North 2634' W. of E-13
Spicer Eng. notes 1982, found nail & cap #7236 2631.5 W of E-13
L.C.R.C. L1623 P1023 1983, Leach set R.R. spike mid point between C-13 & E-13
2634.76 N.89°E. to E-13

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

8-28-97 [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found R.R. spike meas'd East 2634.50 to E-13 on line between C-13 & E-13.
Recovered one witness from LCRC L1623 P1023, N.35°W 136.13 to SE cor. brick wall (M 136.00)
Approved by Peer Group 8-28-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Replaced R.R. spike with 5/8" re-rod, Sag. Co. remon cap mon box 9-17-97.
N.30°W. 136.00 SE corner brick wall of house.
N 32.36 nail & cap E side fence post.
S.30°W. 30.01 nail & cap E side 10" Poplar.



Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612