

MAR 18 1998

SECTION

SAGINAW COUNTY RE-MON 1997
LAND CORNER RECORDATION CERTIFICATE RECORDED & FILED
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Birch Run Township

Saginaw (County)	Located in:	Corner Code #
1. Public Land Survey	T 10N R 6E	E-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

SEP 25 3 25 PM '97

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

LIBER 2027 PAGE 95

Liber 7 Page 135

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald C. Prevost, in a field survey on 5-7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 Post set by J. Wampler 1822
Beech 7 in N.63 W. 32 L
Beech 12 in S.13 W. 48 L
L.C.R.C. L1 P 95 J. Martin, 1971 1" iron bar fnd.
L.C.R.C. L1 P181 N.C. Jones, 1972 3/4" rod, set mon box M.D.O.T.
L.C.R.C. L5 P 53 Folkens, 1980 3/4" iron pin/mb fnd.

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

6-26-97 [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found 1" bar in mon box. 5-7-97
All witness from L1 P95 gone.
Recovered one witness from L1 P181 N.25°W. T. pole 54.71 (54.75)
Recovered one tie from L1 P181 East 52.85 cor E-1 T.9 N.-R.6 E. (M52.98)
Recovered one witness from L5 P53 N.35°E. 51.89 PK/flag SW face P.P. (M51.56)
Recovered one witness from L5 P53 N.40°W. 54.59 PK/flag SW face T.P. (M54.75)
Approved by Peer Group 6-26-97.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Replaced 1" bar with 5/8" re-rod, Sag. Co. Re-mon cap in ext'g mon box 7-1-97.
N.45°E. 51.56 PK w/ribbon W side p. pole.
N.40°W. 54.75 nail & tag W side p. pole.
S.50°E. 43.78 nail & ribbon NE side 30" Maple.
East 52.98 1/2" rod in mon box (E-1 T.9 N.-R.6 E.)



Signed by Ronald C. Prevost
Ronald C. Prevost

Date 9-25-97

Surveyor's Michigan License No. 24612