

APPROVED BY PEER GROUP

P.A. 345 OF 1990

SAGINAW COUNTY

9-18-97

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

1997 SEP 26 P 3: 27

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

For corners in **SAGINAW COUNTY REMONUMENTATION**

SAGINAW Located in: B'RUN TWP. Corner Code #  
(County)

- |                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | <u>T 10N R 6E</u>       | <u>F-13</u> |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

LIBER 2027 PAGE 458

*Lib 7 Page 149*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	8		5		4		3		2		1	
3												
4	7		6		5		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, BRIAN D FERGUSON in a field survey on JUNE 17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13: WOOD POST SET BY WAMPLER IN 1822

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13: FOUND 1/2" SQUARE IRON ROD  
LCRC RECORDED IN L 1 PG 180  
RECORDED SURVEYS L 1659 PG 354

ACCEPTED BY THE PEER REVIEW GROUP AS THE BEST  
AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13: SET 5/8" ROD W/3" BRASS CAP IN MONUMENT BOX  
EAST 42.93' "T" IRON IN PVM'T (F-1, T9N-R6E)  
N10W 25.04' SE FCE 8" MAPLE TREE  
S30E 80.25' TOP CTR MBT RISER  
SOUTH 6.20' EDGE OF PAVEMENT



Signed by

*Brian D Ferguson*

Date

SEPTEMBER 25, 1997

Surveyor's Michigan License No.

26454

SURVEY &  
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1971  
REVISED JAN., 1981  
REVISED OCT., 1991

MAR 18 1998

SECTION