

LAND CORNER RECORDATION CERTIFICATE RECORDED/FILED
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SAGINAW COUNTY REMONUMENTATION**

SAGINAW Located in: B'RUN TWP. Corner Code #
 (County)

1. Public Land Survey	<u>T 10N R 6E</u>	<u>J-13</u>
	T _____	_____
2. Property Controlling in Section	S _____	_____
	S _____	_____
3. Miscellaneous Property in Sec.	S _____	_____
	S _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1997 SEP 26 P 3: 29
 MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY, MI.
 LIBER 2027 PAGE 462
Liber 7 Page 153
 Register of Deeds Stamp & File Number

I, BRIAN D FERGUSON, in a field survey on JUNE 17, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-13: WOOD POST SET BY WAMPLER IN 1822

**SURVEY &
 REMONUMENTATION**

MAR 18 1998

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY

9-18-97 *[Signature]*

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13: FOUND 3/4" IRON PIPE

AGREES WITH LOCATION BASED ON FIELD NOTES AND SECTION COMPUTATIONS BY RC ASSOCIATES AND LEACH ENGINEERING CO.

ACCEPTED BY THE PEER REVIEW GROUP AS THE BEST
 AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13: SET 5/8" ROD W/3" BRASS CAP IN MONUMENT BOX
 N30E 43.15' NAIL SE FCE 48" OAK TREE
 EAST 47.64' 1/2" REROD IN ROAD (J-1, T9N-R6E)
 N45W 47.65' PK NAIL IN S FCE 14" MAPLE TREE
 SOUTH 8.04' EDGE OF PAVEMENT



Signed by *Brian D Ferguson*
 Surveyor's Michigan License No. 26454

Date SEPTEMBER 25, 1997