

APPROVED BY PEER GROUP  
 P.A. 345 OF 1990  
 SAGINAW COUNTY  
 7-23-97 *BMF*

1997 REMONUMENTATION PROGRAM  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED  
 LIBER 2028 PAGE 432

1997 OCT -3 A 8: 28

MILDRED M. DODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY, MI.

*Sheet 7 Page 177*

Register of Deeds Stamp & File Number

<u>SAGINAW</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>06E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JONATHAN M. FIELD, in a field survey on JULY 8 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 1821 GLO; WAMPLER, D.S.; SET 1/4 SEC. POST; BEECH 8 S19 1/2W 15LKS., BEECH 16 N74E 27LKS.  
 1887 GOODALE, C.S.; SURVEY OF SEC. 1&12 T10N-R6E, PG. 232; OLD STAKE & WIT.  
 1978 HAMMOND ENG.; HAMMOND, RLS#8890; SURVEY L.1546, PG.1200-1201; 3/4" PIPE; SE 36.35' CTR. ST. SIGN POST, SW 19.81' NAIL NW FACE TP  
 1979 HAMMOND ENG.; HAMMOND, RLS#8890; SURVEY L.1572, PG.164-166; 3/4" PIPE; SAME WITS AS 1978 SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1997 ROWE; FIELD, PS#37276; FND. 3/4" PIPE 6' W. OF C/L REESE ROAD, NO PREVIOUS WITNESSES REMAIN.

ACCEPTED FND. PIPE AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-2 REPLACED FND. 3/4" PIPE W/ 5/8" ROD & STD. REMON. CAP IN MON. BOX  
 N60°E, 56.73' P-K NAIL W/TAG #37276 IN NW FACE P.POLE  
 N45°W, 27.03' NAIL W/TAG #37276 IN SW FACE 18" OAK  
 N12°W, 83.89' NAIL W/TAG #37276 IN NE FACE 18" OAK  
 S40°E, 80.41' NAIL W/TAG #37276 IN NE FACE 18" MAPLE  
 NORTH, 22.86' FND. 3/4" PIPE



Signed by *Jonathan M. Field* Date 9-25-97  
 Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JUL 22, 19  
 REVISED MAY 14, 19  
 REVISED JAN, 19  
 ADAPTED FOR WORD PROCESSING MARCH, 19

SURVEY &  
 REMONUMENTATION

MAR 18 1998

SECTION