

LAND CORNER RECORDATION CERTIFICATE RECORDED/FILED
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SAGINAW COUNTY REMONUMENTATION**

1997 SEP 26 P 3: 26

MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY, MI.

LIBER 2027 PAGE 450

Liber 7 Page 141
 Register of Deeds Stamp & File Number

SAGINAW Located in: B'RUN TWP. Corner Code #
 (County)

1. Public Land Survey T 10N R 6E M-10
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, BRIAN D FERGUSON, in a field survey on JUNE 17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-10: WOOD POST SET BY WAMPLER IN 1822

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY

9-18-97 BDF

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10: FOUND 3/4" IRON PIPE
 LCRC RECORDED IN L 2 PG 218, L 3 PG 220

ACCEPTED BY THE PEER REVIEW GROUP AS THE BEST
 AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10: SET 5/8" ROD W/3" BRASS CAP IN MONUMENT BOX
 EAST 51.75 NAIL IN S. FCE PWR POLE
 N45E 85.43' PK IN SE FCE PWR POLE
 N30W 39.87' CTR STREET SIGN POST
 S45W 35.35' CTR LINE 36" CMP @ END
 NORTH 7.73' "T" IRON USED AS M-10



Signed by Brian D Ferguson
 Surveyor's Michigan License No. 26454
 SURVEY & REMONUMENTATION

Date SEPTEMBER 26, 1997

MAR 18 1998

SECTION