

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 SEP 26 P 3: 26

For corners in SAGINAW COUNTY REMONUMENTATION

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

SAGINAW
(County)

Located in: B'RUN TWP. Corner Code #

- 1. Public Land Survey T 10N R 6E M-12
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

LIBER 2027 PAGE 448

Lib 2027 Page 139

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

BRIAN D FERGUSON in a field survey on JUNE 17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12: WOOD POST SET BY WAMPLER IN 1822

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

9-18-97 *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12: FOUND 3/4" PIPE
LCRC RECORDED IN L 3 PG 86

SURVEY &
REMONUMENTATION

MAR 18 1998

ACCEPTED BY THE PEER REVIEW GROUP AS THE BEST
AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12: SET 5/8" ROD W/3" BRASS CAP IN MONUMENT BOX
S85W 55.15' E FCE 18" DECIDUOUS TREE
N20E 49.76' S FCE 12" DECIDUOUS TREE
S30E 46.92' NW FCE 12" DECIDUOUS TREE
N20W 56.80' TOP CTR OF LARGE ROCK IN YARD



Signed by *Brian D Ferguson*
Surveyor's Michigan License No. 26454

Date SEPTEMBER 25, 1997